

SOIL DATA

SYMBOL	DESCRIPTION	PRIME FARMLAND	HIGHLY ERODIBLE	HYDRIC
23	GLENELG SILT LOAM 8-15% SLOPES	YES	NO	NO

NOTE: ALL SOIL ON SITE IS 23, GLENELG SILT LOAM.

FOREST CONSERVATION WORKSHEET
OFFUTT ESTATES

NET TRACT AREA:

A. Total tract area		1.03
B. Land dedication acres (parks, county facility, etc.)		0.00
C. Land dedication for roads or utilities (not being constructed by this plan)		0.00
D. Area to remain in commercial agricultural production/use		0.00
E. Other deductions (specify)		0.00
F. Net Tract Area		1.03

LAND USE CATEGORY: (from Trees Technical Manual)
Input the number "1" under the appropriate land use, limit to only one entry.

ARA	MDR	IDA	HDR	MPD	CIA
0	0	0	1	0	0

G. Afforestation Threshold	15%	x F = 0.15
H. Conservation Threshold	20%	x F = 0.21

EXISTING FOREST COVER:

I. Existing forest cover	0.00
J. Area of forest above afforestation threshold	0.00
K. Area of forest above conservation threshold	0.00

BREAK EVEN POINT:

L. Forest retention above threshold with no mitigation	0.00
M. Clearing permitted without mitigation	0.00

PROPOSED FOREST CLEARING:

N. Total area of forest to be cleared	0.00
O. Total area of forest to be retained	0.00

PLANTING REQUIREMENTS:

P. Reforestation for clearing above conservation threshold	0.00
Q. Reforestation for clearing below conservation threshold	0.00
R. Credit for retention above conservation threshold	0.00
S. Total reforestation required	0.00
T. Total afforestation required	0.15
U. Credit for landscaping (may not exceed 20% of "T")	0.00
V. Total reforestation and afforestation required	0.15

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- LOD
- LIMIT OF DISTURBANCE
- TREE LINE
- EXISTING OVERHEAD LINES
- EXISTING WATER LINES
- EXISTING SEWER LINES
- EXISTING STORM DRAIN
- EXISTING UNDERGROUND GAS LINES
- EXISTING UNDERGROUND ELECTRICAL LINES
- EXISTING UNDERGROUND TELEPHONE / CABLE LINES
- SUPER SILT FENCE W/ ROOT PRUNING
- ROOT PRUNING
- SUPER SILT FENCE
- EXISTING TREE CANOPY
- EXISTING WOOD FENCE
- EXISTING WIRE FENCE
- EXISTING CHAIN LINK FENCE
- EXISTING DECIDUOUS TREE
- EXISTING CONIFER TREE
- EXISTING TREE WITH CRITICAL ROOT ZONE
- EXISTING TREE TO BE REMOVED

MITIGATION TREE LANDSCAPE SCHEDULE

SYMBOL	QTY	COMMON NAME	SCIENTIFIC NAME	SIZE	CREDIT	REMARKS
SG	9	AMERICAN SWEET GUM	LIQUIDAMBAR STYRACIFLUA	3" CAL	27"	B&B
WO	6	WILLOW OAK	QUERCUS PHELLOS	3" CAL	20"	B&B
SM	3	SOUTHERN MAGNOLIA	MAGNOLIA GRANDIFLORA	3" CAL	12"	B&B

VARIANCE TREE MITIGATION

TO COMPENSATE FOR THE REMOVAL OF SEVEN ONSITE VARIANCE TREES (264"), 66" PLANTING MITIGATION IS REQUIRED. WE PROPOSE TO PLANT A TOTAL OF 66" AS NOTED ON THE MITIGATION LANDSCAPE SCHEDULE THIS SHEET AND AS SHOWN THUS

VICINITY MAP

SCALE: 1" = 2000'
ADC MAP 66 - GRID 2F

GENERAL NOTES

1. SITE ADDRESS IS 5421 HILLERY WAY, ROCKVILLE, MD 20852
2. TAX I.D. NUMBER: 04-00288877
3. PLAT REFERENCE: PLAT BOOK 83, LOT PLAT 1985, LOT 8.
4. DEED REFERENCE: LIBER 50162 FOLIO 11.
5. SITE IS LOCATED ON TAX MAP: HX-431.
6. SITE IS LOCATED ON WSSC 200 SHEET No. 204 NW 05.
7. EXISTING WATER AND SEWER CATEGORY IS W-1 & S-1.
8. SITE HAS EXISTING WATER AND SEWER MAINLINES.
9. EXISTING ZONING IS I-1 12.5
10. EXISTING SOILS ARE 23, GLENELG SILT LOAM, 8-15% SLOPES.
11. BOUNDARY SHOWN FROM ROCKVILLE CREEK ENG. PLATS.
12. TOPOGRAPHY BY FIELD SURVEY BY D.G. ASSOCIATES, INC. JUNE 2014.
13. WATERSHED: ROCK CREEK, CLASS I
14. UTILITY COMPANIES:
ELECTRIC: PEPCO
WATER & SEWER: WSSC
TELEPHONE: VERIZON
CATV: COMCAST
15. OWNER / APPLICANT
WHITE FLINT 7 LLC, INC.
ALEXANDER & MEDLIN LIVAULT
6700 ELROY LANE
ROCKVILLE, MD 20852
301-213-0440
CONTACT: MEDY LIVAULT
16. AREA OF DISTURBANCE = 44,155 S.F.
17. HILLERY WAY SHALL BE DESIGNED AS A TERTIARY RESIDENTIAL ROADWAY, AS MODIFIED STANDARD NO. MC-2001.01.
HILLERY WAY IS A TERTIARY STREET.
18. DEVELOPMENT DATA, CALCULATIONS BASED ON THE STANDARDS SET FORTH IN THE OPTIONAL METHOD OF DEVELOPMENT ZONING ORDINANCE SECTION 59-C-1.73.
19. THE BUILDING SETBACK HAS BEEN SCALED FROM 30' TO 20' PER FOOTNOTE 5 IN ZONING ORDINANCE SECTION 59-C-1.732, STATING, "UNLESS A MORE GENEROUS FORM OF DEVELOPMENT CAN BE DEMONSTRATED BY THE APPLICANT TO THE SATISFACTION OF THE PLANNING BOARD, UNDER THE STREET, SIDE AND REAR LOT LINE RESTRICTIONS AS DEFINED IN THIS SECTION.
20. ALL SIDEWALKS ARE TO BE ADA COMPLIANT.

GENERAL NRI NOTES

1. THERE ARE NO NON-TIDAL WETLANDS IDENTIFIED ON THE SITE.
2. THERE ARE NO CEMETERIES ON THE SITE.
3. THERE IS NO 100 YEAR FLOOD PLAIN ON THE SITE.
4. THERE IS NO FOREST ON THE SITE.
5. THERE ARE NO STATE/COUNTY CHAMPION TREES, OR ANY 75% OF STATE CHAMPION TREES ON THIS SITE.
6. A RESPONSE W/S RECEIVED FROM THE DEPARTMENT OF NATURAL RESOURCES ON 8/17/14 THAT THERE ARE NO RARE, THREATENED OR ENDANGERED SPECIES WITHIN THE BOUNDARIES OF THE SITE.
7. THERE ARE NO CULTURAL OR HISTORIC FEATURES ON THE SITE AND IT IS NOT ON THE LOCATIONAL ATLAS OF HISTORICAL SITES.
8. NO RARE, THREATENED, OR ENDANGERED SPECIES WERE OBSERVED ON THE PROPERTY.
9. TREES WERE MEASURED WITH A DIAMETER TAPE BY DEAN PACKARD ON JUNE 27, 2014.
10. EXACT LOCATION OF ROOT PRUNING AND FENCING TO BE DETERMINED BY THE ARBORIST BASED ON THE SITE CONDITIONS.

RESOURCE DATA TABLE

ACREAGE OF TRACT	1.03 ACRES
ACREAGE OF TRACT REMAINING IN AGRICULTURE	0.00 ACRES
ACREAGE OF ROAD AND UTILITY R/W WHICH WILL NOT BE IMPROVED AS PART OF DEV. APPLICATION	0.00 ACRES
ACREAGE OF EXISTING FOREST	0.00 ACRES
ACREAGE OF TOTAL FOREST RETENTION	0.00 ACRES
ACREAGE OF TOTAL FOREST CLEARED	0.00 ACRES
LAND USE CATEGORY	HDR
AFFORESTATION THRESHOLD	0.00 ACRES
CONSERVATION THRESHOLD	0.00 ACRES
ACREAGE OF FOREST RETAINED, CLEARED AND PLANTED WITHIN WETLANDS	0.00/0.00/0.00 ACRES
ACREAGE OF FOREST RETAINED, CLEARED AND PLANTED WITHIN 100 YR FLOODPLAIN	0.00/0.00/0.00 ACRES
ACREAGE OF FOREST RETAINED, CLEARED AND PLANTED WITHIN STREAM BUFFERS	0.00/0.00/0.00 ACRES
ACREAGE OF FOREST RETAINED, CLEARED AND PLANTED WITHIN PRIORITY USES	0.00/0.00/0.00 ACRES
LINEAR EXTENT & AVERAGE WIDTH OF STREAM BUFFER	0.00/0.00

THE ENTIRE AFFORESTATION/REFORESTATION REQUIREMENT WILL BE MET BY TAKING THE ACREAGE TO AN OFF-SITE FOREST MITIGATION BANK.

SIGNIFICANT / SPECIMEN TREE SUMMARY

TREE No.	COMMON NAME	BOTANICAL NAME	% CRZ IMPACT	RETAIN/ REMOVE	DBH (inches)	TREE CONDITION	COMMENTS
100	SILVER MAPLE	ACER SACCHARINUM	50	REMOVE	45"	FAIR	HEAVY WK, POOR STRUCTURE
200	RED MAPLE	ACER RUBRUM	100	REMOVE	26"	GOOD	
300	WHITE OAK	QUERCUS ALBA	45	REMOVE	33"	GOOD	MULTI-STEM >30", WK
400	WATER OAK	QUERCUS NIGRA	45	REMOVE	37"	FAIR	MULTI-STEM >30", DEAD WOOD, HEAVY IVY
500	RED MAPLE	ACER RUBRUM	37	REMOVE	30"	FAIR	HEAVY WK, CURVED TRUNK, LEANING
600	RED MAPLE	ACER RUBRUM	37	REMOVE	28"	FAIR	HEAVY WK, CURVED TRUNK, LEANING
700	RED MAPLE	ACER RUBRUM	32	REMOVE	30"	POOR	HEAVY WK, LIGHTNING DAMAGE, DEAD WOOD
800	RED MAPLE	ACER RUBRUM	50	REMOVE	29"	FAIR	HEAVY WK, LIGHTNING DAMAGE, DEAD WOOD
900	WATER OAK	QUERCUS NIGRA	25	REMOVE	25"	POOR	HEAVY WK, POOR STRUCTURE
1000	SYCAMORE	PLATANUS OCCIDENTALIS	50	REMOVE	40"	GOOD	HEAVY IVY
1100	WHITE PINE	PINUS STROBUS	25	REMOVE	24"	GOOD	
1200	WHITE PINE	PINUS STROBUS	25	REMOVE	24"	GOOD	
1300	WHITE PINE	PINUS STROBUS	37	REMOVE	28"	GOOD	
1400	WHITE PINE	PINUS STROBUS	75	REMOVE	36"	GOOD	
2000	SILVER MAPLE	ACER SACCHARINUM	30	REMOVE	30"	FAIR/GOOD	DEAD WOOD, 30%

(S) - SIGNIFICANT TREE
(ST) - SPECIMEN TREE
(V) - VARIANCE/COMMENT TREE

SIGNIFICANT / SPECIMEN TREE SUMMARY

TREE No.	COMMON NAME	BOTANICAL NAME	% CRZ IMPACT	RETAIN/ REMOVE	DBH (inches)	TREE CONDITION
1500	SILVER MAPLE	ACER SACCHARINUM	32	REMOVE	46"	FAIR/GOOD
1700	RED MAPLE	ACER RUBRUM	25	REMOVE	24"	FAIR/GOOD
1800	RED MAPLE	ACER RUBRUM	50	REMOVE	30"	GOOD
1900	WHITE PINE	PINUS STROBUS	40	REMOVE	36"	GOOD
2000	WHITE PINE	PINUS STROBUS	22	REMOVE	36"	GOOD
2100	WHITE PINE	PINUS STROBUS	22	REMOVE	36"	GOOD
2200	BLUE SPRUCE	PICEA PUNGENS	50	REMOVE	36"	GOOD
2300	TULIP POPLAR	LIRIODENDRON TULIPIFERA	0	REMOVE	30"	GOOD
2400	TULIP POPLAR	LIRIODENDRON TULIPIFERA	0	REMOVE	30"	GOOD
2500	RED MAPLE	ACER RUBRUM	0	REMOVE	30"	GOOD
2600	RED MAPLE	ACER RUBRUM	12	REMOVE	40"	GOOD

GRAPHIC SCALE: 1"=30'

MISS UTILITY

CALL "MISS UTILITY" AT 1-800-257-7777, 48 HOURS PRIOR TO THE START OF WORK. THE EXCAVATOR MUST NOTIFY ALL PUBLIC UTILITY COMPANIES WITH UNDERGROUND FACILITIES IN THE AREA OF PROPOSED EXCAVATION AND HAVE THOSE FACILITIES LOCATED BY THE UTILITY COMPANIES PRIOR TO COMMENCING EXCAVATION. THE EXCAVATOR IS RESPONSIBLE FOR COMPLIANCE WITH THE REQUIREMENTS OF CHAPTER 36T, OF THE MONTGOMERY COUNTY CODE.

PACKARD & ASSOCIATES, LLC
CIVIL ENGINEERS * SURVEYORS * LAND PLANNERS
19220 FREDERICK ROAD, SUITE 300
GAITHERSBURG, MARYLAND 20877
PHONE (301) 208-0250 FAX (301) 208-1270

DESCRIPTION
REVISIONS

PRELIMINARY FOREST CONSERVATION PLAN
OFFUTT ESTATES
120150040
PROPERTY OF WHITE FLINT PARK, INC.
RECORDED IN PLAT BOOK 83, PLAT 1985
BEING LOT 8 IN HILLERY WAY
ROCKVILLE ELECTION DISTRICT No. 4 MONTGOMERY COUNTY, MARYLAND

SCALE: 1" = 30'
DESIGN
DATE: 8-28-18
ACAD FILE NAME: OFFUTTHILLARY 2014

Plan Prepared by:

DEAN PACKARD
Qualified Professional
Cert. No. 18-06-01

SHEET 1 OF 1

Attachment 10