

4/17/09

17200 CASHELL ROAD

Attn: JACK GATES

301-774-7700

ROCKVILLE, MARYLAND 20853

Root pruning note removed

Donald W. Rohrbaugh, II

AFRIL 17, 2009

Md. Reg. Landscape Architect #491

20410 Observation Drive - Suite 205

Engineering - Surveying - Planning - Landscape Architecture


Fax-(301)-540-7991

Germantown - Maryland - 20876

(301)-540-7990

8th ELECTION DISTRICT

MONTGOMERY COUNTY, MARYLAND



TRFF PROTECTION LIST

REE #	COMMON NAME	CONDITION	DBH SIGNIF	ICANT TREE (Y/N)	CRZ AREA *	% CRZ SAVED	SAVE / REMOVE	COMMENTS
1	Sugar Maple	Good	30"	Y (Specimen)	5,160 sq.ft.*	100	Save	
2	Pin Oak	Good	27"	Υ	1,940 sq.ft.*	100	Save	
3	Kentucky Coffeetree	Good	9"	N	570 sq.ft.	100	Save	
4	Kentucky Coffeetree	Good	14"	N	1,130 sq.ft.*	100	Save	
5	Kentucky Coffeetree	Good	14"	N	970 sq.ft.*	100	Save	
6	Norway Maple	Good	20"	Υ	650 sq.ft.*	85	Save	In concrete cut-out
7	Kentucky Coffeetree	Good	24"	Υ	1,640 sq.ft.*	65	Save	Root prune
8	Kentucky Coffeetree	Good	14"	N	890 sq.ft.*	100	Save	
9	Kentucky Coffeetree	Good	12"	N	1,020 sq.ft.	80	Save	Root prune
10	Kentucky Coffeetree	Good	15/15" (Dbl.)	N	1,330 sq.ft.*	0	Remove	On L.O.D.
11	Yew (tree form pruned)	Good	N/A - multi	N	880 sq.ft.*	50	Save	Owner desires to attempt to save as unique plant; root & crown prune
12	Crabapple	Good	18"	N	2,290 sq.ft.	93	Save	
13	White Pine	Good	18"	N	2,290 sq.ft.	60	Save	No grading in CRZ, high survivabili potential (White Pine)
14	Crabapple	Good	18"	N	2,180 sq.ft.*	70	Save	No grading in CRZ
15	Crabapp1e	Good	18"	N	2,130 sq.ft.*	100	Save	
16	Bald Cypress	Good	12/15" (Dbl.)	N	1,900 sq.ft.*	50	Remove	Less than 3 ft. from L.O.D.
17	Bald Cypress	Good	12/9" (Dbl.)	N	770 sq.ft.*	80	Save	Root prune
18	Bald Cypress	Good	9" ` `	N	510 sq.ft.*	94	Save	
19	White Pine	Good	24"	Υ	2,890 sq.ft.*	74	Save	Root prune
20	White Pine	Good	26"	Υ	2,860 sq.ft.*	100	Save	Protected by cart path
21	White Pine	Fair	24"	Υ	2,020 sq.ft.*	100	Save	Protected by cart path
22	White Pine	Good	28"	Υ	4,280 sq.ft.*	80	Save	Root prune
23	Weeping Cherry	Good	4"	N	70 sq.ft.*	0	Remove	Within disturbed area
24	Weeping Cherry	Good	6"	N	160 sq.ft.*	100	Save	

* = Indicates Critical Root Zones impacted (reduced) by adjacent pavement, buildings or other impervious
site elements. Base CRZ is 1.5 ft. radius per DBH inch (per Trees Technical Manual method of determination).

FOREST CONSERVATION NOTES

Sequence of Events for Property Owners Required to Comply With Forest Conservation and/or Tree-Save Plans

Pre-Construction

- 1. An on-site pre-construction meeting is required after the limits of disturbance have been staked and flagged, but before any clearing or grading begins. The property owner should contact the Montgomery County Planning Department inspection staff before construction to verify the limits of disturbance and discuss tree protection and tree care measures. The developer's representative, construction superintendent, ISA certified arborist or Maryland-licensed tree expert that will implement the tree protection measures, forest conservation inspector, and Department of Permitting Services (DPS) sediment control inspector should attend this pre-construction meeting.
- 2. No clearing or grading shall begin before stress-reduction measures have been
- implemented. Appropriate measures may include, but are not limited to:
- Root pruning b. Crown reduction or pruning
- c. Watering
- d. Fertilizing
- e. Vertical mulching f. Root aeration matting

Measures not specified on the forest conservation plan may be required as determined by the forest conservation inspector in coordination with the

- 3. A Maryland-licensed tree expert or an International Society of Arboriculturecertified arborist must perform all stress reduction measures. Documentation of stress reduction measures must be either observed by the forest conservation inspector or sent to the inspector at 8787 Georgia Avenue, Silver Spring, MD 20910. The forest conservation inspector will determine the exact method to convey the stress reductions measures during the pre-construction meeting.
- 4. Temporary tree protection devices shall be installed per the Forest Conservation Plan/Tree Save Plan and prior to any construction activities. Tree protection fencing locations should be staked prior to the pre-construction meeting. The forest conservation inspector, in coordination with the DPS sediment control inspector, may make field adjustments to increase the survivability of trees and forest shown as saved on the approved plan. Temporary tree protect devices may include:
- a. Chain link fence (four feet high)

- b. Super silt fence with wire strung between support poles (minimum 4 feet
- high) with high visibility flagging. c. 14 gauge 2 inch x 4 inch welded wire fencing supported by steel T-bar posts (minimum 4 feet high) with high visibility flagging.
- 5. Temporary protection devices shall be maintained and installed by the contractor for the duration of construction project and must not be altered without prior approval from the forest conservation inspector. No equipment, trucks, materials, or debris may be stored within the tree protection fence areas during the entire construction project. No vehicle or equipment access to the fenced area will be permitted. Tree protection shall not be removed without prior approval of forest conservation inspector.
- 6. Forest retention area signs shall be installed as required by the forest conservation inspector, or as shown on the approved plan.

long-term protection measures to be installed.

7. Long-term protection devices will be installed per the Forest Conservation Plan/Tree Save Plan and attached details. Installation will occur at the appropriate time during the construction project. Refer to the plan drawing for

During Construction


8. Periodic inspections by the forest conservation inspector will occur during the construction project. Corrections and repairs to all tree protection devices, as determined by the forest conservation inspector, must be made within the

timeframe established by the inspector.

Post-Construction


- 9. After construction is completed, an inspection shall be requested. Corrective
- measures may include:
- a. Removal and replacement of dead and dying trees b. Pruning of dead or declining limbs
- c. Soil aeration d. Fertilization
- e. Watering
- f. Wound repair g. Clean up of retention areas
- 10. After inspection and completion of corrective measures have been undertaken, all temporary protection devices shall be removed from the site. Removal of tree protection devices that also operate for erosion and sediment control must be coordinated with both the Department of Permitting Services and the forest conservation inspector. No additional grading, sodding, or burial may take place after the tree protection fencing is removed.

STRESS REDUCTION MEASURE(3) ROOT PRUNING TREE PROTECTION FENCE ROOT PRUNING TRENCH 1. Retention Areas will be set as part of the review process. 2. Boundaries of Retention Areas should be staked and flagged prior to trenching. 3. Exact location of trench should be identified. 4. Trench should be immediately backfilled with soil revoved or other high organic 5. Roots should be cleanly cut using vibratory knife of other acceptable equipment.



TREE PROTECTION FENCE - WELDED WIRE (48" Ht.)

NOT TO SCALE



Sign Detail

All field inspections must be requested by the applicant. Inspections must be conducted as

Tree Save Plans and Forest Conservation Plans without Planting Requirements

- 1. After the limits of disturbance have been staked and flagged, but before any clearing or
- grading begins 2. After necessary stress reduction measures have been completed and protection
- measures have been installed, but before any clearing and grading begin. 3. After completion of all construction activities, but before removal of tree protection fencing, to determine the level of compliance with the provision of the forest conservation.

Additional Requirements for Plans with Planting Requirements

- 4. Before the start of any required reforestation and afforestation planting 5. After the required reforestation and afforestation planting has been completed to verify that the planting is acceptable and prior to the start the maintenance period.
- 6. At the end of the maintenance period to determine the level of compliance with the provisions of the planting plan, and if appropriate, release of the performance bond.

* M-NCPPC Inspection phone number: (301)495-4581

BUILDING PERMIT NOTE

Building Permit shall not be released until the M-NCPPC forest conservation inspector has signed off on the tree protection measures prescribed on these drawings.

> THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION Amendment to FINAL FOREST CONSERVATION PLAN APPROVAL

Plan No. CBA - 2724-C

SS SITE SOLUTIONS INCORPORATED 20410 Observation Drive - Suite 208 Germantown - Maryland - 20876 (301)-540-7990 Fax-(301)-540-7991 Engineering - Surveying - Planning - Landscape Architecture Md. Reg. Landscape Architect #491 APRIL 17, 2009



NORBECK COUNTRY CLUB 17200 CASHELL ROAD ROCKVILLE, MARYLAND 20853 Attn: JACK GATES 301-774-7700

FOREST CONSERVATION PLAN / TREE PROTECTION NORBECK COUNTRY CLUB PARCEL P400, L. 1811 F. 251 8th ELECTION DISTRICT

MONTGOMERY COUNTY, MARYLAND

As Noted 4/17/2009 PROJ. No. 1641 E-