


SITE: SATELLITE VIEW

CHABERTON SOLAR SUGARLOAF LLC

CHABERTON SOLAR SUGARLOAF

5,922.24 kWdc / 4,000.00 kWac SOLAR GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 MONTGOMERY COUNTY, MD 39.2080°N, -77.4233°W

10% DESIGN PACKAGE



SHEET INDEX					
SHEET NUMBER	SHEET TITLE	REVISION			
G-001	COVER SHEET & INDEX	D			
G-010	GENERAL SYMBOLS & NOTES	A			
E-001	ELECTRICAL SITE PLAN	D			
E-100	ELECTRICAL SINGLE LINE DIAGRAM	Α			
E-200	EQUIPMENT PAD DETAILS	A			
E-500	EQUIPMENT DATASHEETS	A			
E-501	EQUIPMENT DATASHEETS	A			
M-001	RACKING DETAILS	A			
M-101	PLANAR STUDY	В			
1 OF 6	COVER SHEET	-			
2 OF 6	EXISTING CONDITIONS PLAN	-			
3 OF 6	PROPOSED SITE PLAN 1	-			
4 OF 6	PROPOSED SITE PLAN 2	-			
5 OF 6	PROPOSED SITE DETAILS	-			
6 OF 6	PROPOSED SITE DETAILS	-			

SYSTEM SUMMARY				
DC SYSTEM SIZE 5,922.24 kWdc				
AC SYSTEM SIZE	4,000.00 kWac			
DC/AC RATIO	1.481			
MODULES	QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV.			
MODULE QUANTITY	9,552			
INVERTERS	CHINT CPS SCH125KTL-DO/US-600 OR EQUIV.			
INVERTER QUANTITY	34			
AZIMUTH/TILT	180° / SINGLE AXIS TRACKER			
PITCH	16.2 ft			

PROJECT

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 39.2080°N, -77.4233°W DEVELOPER

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852



D	LAYDOWN UPDATE	07/30/2024	APPROVED BY:
С	ROAD LAYOUT UPDATE	07/24/2024	CHECKED BY:
В	PIER HEIGHT REVISION	07/02/2024	EJA DESIGNED BY:
REV.	DESCRIPTION	DATE	AOK

CONSTRUCTION

10% DESIGN

01/04/2024

DRAWING TITLE

COVER SHEET &

INDEX

REVISION DRAWING NO.

NOT FOR

DRAWING NO.

G-001

	ABBREVIATIONS	STA	NDARD SYMBOLS	EXAMPLE WILDFLO	WER SEE	DING MIX	K LIST
A AC	AMPERES ALTERNATING CURRENT	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	BREAKER	DESCRIPTION	BULK QTY	PLS QTY	UOM
AF	AMPERE FRAME	· \	DIVEAREN	ROUNDSEED PANICGRASS	0.377	0.350	LB PLS
AHJ	AUTHORITY HAVING JURISDICTION			PATH RUSH, PA ECOTYPE	0.066	0.060	LB PLS
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	52R	BREAKER WITH RECLOSER	PURPLE LOVEHRASS, FORT INDIANTOWN GAP, PA ECOTYPE	0.023	0.020	LB PLS
	AMERICAN SOCIETY OF CIVIL			SENSITIVE PEA, NC ECOTYPE	0.082	0.080	LB PLS
ASCE	ENGINEERS	$ \langle x \rangle $	CONDUCTOR IDENTIFIER	BLACKEYED SUSAN	0.123	0.120	LB PLS
AT	AMPERE TRIP			LANCELEAF COREOPSIS	0.113	0.100	LB PLS
AUX	AUXILIARY	Ω	CURRENT TRANSFORMER	MISTFLOWER, VA ECOTYPE	0.008	0.005	LB PLS
AWG	AMERICAN WIRE GAUGE			BUTTERFLY MILKWEED	0.020	0.015	LB PLS
BESS	BATTERY ENERGY STORAGE SYSTEM		DISCONNECT SWITCH	AROMATIC ASTER, PA ECOTYPE	0.019	0.010	LB PLS
BKR	BREAKER			NARROWLEAF MOUNTAINMINT	0.024	0.020	LB PLS
CAT	CATEGORY	-/		GOLDEN ALEXANDERS, PA ECOTYPE	0.023	0.020	LB PLS
CEH	CHABERTON ENERGY HOLDINGS		ELECTRIC POLE	NARROWLEAF BLUE EYED GRASS	0.032	0.030	LB PLS
CKT	CIRCUIT			EASTERN GRAY BEARDTONGUE	0.005	0.005	LB PLS
СТ	CURRENT TRANSFORMER			HAIRY BEARDTONGUE	0.006	0.005	LB PLS
DAS	DATA ACQUISITION SYSTEM] (x)	EQUIPMENT IDENTIFIER	CALICO ASTER	0.013	0.010	LB PLS
DC	DIRECT CURRENT			AUTUMN BENTGRASS, ALBANY PINE	0.157	0.150	LB PLS
EGC	EQUIPMENT GROUNDING CONDUCTOR	占		BUSH, NY ECOTYPE	0.157	0.150	LD PLS
EMT	ELECTRIC METALLIC TUBING		FUSE				
EPC	ENGINEERING, PROCUREMENT, &	十		POLLINATOR NOTES:			
	CONSTRUCTION COMPANY						
EST	ESTIMATED		INVERTER	1. SUGGESTED SEED RATE IS 3 PLS POU	•	NG WITH 30 POUN	IDS OF
EXIST	EXISTING			COVER CROP (GRAIN OATS OR GRAIN			
GEC	GROUND ELECTRODE CONDUCTOR	35	OUTLET	2. POLLINATOR SEEDING MIX SUBJECT		_	CEEDING
GFCI	GROUND FAULT CURRENT	Ψ	POTENTIAL TRANSFORMER	3. ALL AREAS WITHIN PROJECT FENCE T	O RECEIVE POLLINA	TOR WILDFLOWER	SEEDING
	INTERRUPTER			IVIIA.			
GND	GROUND	-{	SURGE ARRESTER				
IC	INTERCONNECTION CUSTOMER	<u></u>					
IEEE	INSTITUTE OF ELECTRICAL AND	1 1					
	ELECTRONICO ENGINEERO	التليا					
150	ELECTRONICS ENGINEERS		TRANSFORMER				
IFC	ISSUED FOR CONSTRUCTION	m	TRANSFORMER				
Imp	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER	m					
Imp Isc	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT	A	NSI STANDARD				
Imp Isc IX	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION	A	NSI STANDARD				
Imp Isc	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE	A Di	NSI STANDARD EVICE NUMBERS				
Imp Isc IX	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS	A	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY				
Imp Isc IX LV MCOV	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE	A Di	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS				
Imp Isc IX LV MCOV MFR	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY	27 50	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY				
Imp Isc IX LV MCOV MFR MPPT	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING	27 50 51	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY				
Imp Isc IX LV MCOV MFR MPPT MV	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE	27 50 51 52	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER				
Imp Isc IX LV MCOV MFR MPPT MV NEC	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN	27 50 51 52	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD SWGR	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD SWITCHGEAR	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD SWGR TBD	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD SWITCHGEAR TO BE DETERMINED	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD SWGR TBD TYP.	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD SWITCHGEAR TO BE DETERMINED TYPICAL	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD SWGR TBD TYP. UL	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD SWITCHGEAR TO BE DETERMINED TYPICAL UNDERWRITERS LABORATORIES	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				
Imp Isc IX LV MCOV MFR MPPT MV NEC NO NTS PLS PRI PSF PT PV QTY SEC SWBD SWGR TBD TYP. UL UOM	ISSUED FOR CONSTRUCTION CURRENT MAXIMUM POWER CURRENT SHORT CIRCUIT INTERCONNECTION LOW VOLTAGE MAXIMUM CONTINUOUS OPERATING VOLTAGE MULTI-FUNCTION RELAY MAXIMUM POWER POINT TRACKING MEDIUM VOLTAGE NATIONAL ELECTRICAL CODE NUMBER / NORMALLY OPEN NOT TO SCALE PURE LIVE SEED PRIMARY POUNDS PER SQUARE FOOT POTENTIAL TRANSFORMER PHOTOVOLTAIC QUANTITY SECONDARY SWITCHBOARD SWITCHGEAR TO BE DETERMINED TYPICAL UNDERWRITERS LABORATORIES UNIT OF MATERIAL	27 50 51 52 59	ANSI STANDARD EVICE NUMBERS UNDERVOLTAGE RELAY INSTANTANEOUS OVERCURRENT RELAY TIMED OVERCURRENT RELAY CIRCUIT BREAKER OVERVOLTAGE RELAY				

PROJECT NOTES:

- PROJECT CONSISTS OF A SINGLE 4.00 MWac INTERCONNECTION TO SERVE POTOMAC EDISON COMMUNITY SOLAR
- 2. PROJECT IS CURRENTLY DESIGNED WITH QCELL Q.TRON XL-G2 620 (620WP) OR EQUIV. MODULES TO BE PROVIDED BY PROJECT OWNER OR EPC.

GENERAL NOTES:

- THIS DESIGN PACKAGE INDICATED THE INTENT OF THE DESIGN AND SHALL BE CONSIDERED DIAGRAMMATIC ONLY OF REQUIRED EQUIPMENT FOR ACCURATE BID PRICING. FULL ENGINEERING DESIGN TO BE SUBMITTED BY EPC AND APPROVED BY CEH. EPC SHALL ENGINEER THE SYSTEM FOR A SAFE AND COMPLIANT SYSTEM AT MAXIMUM ENERGY PRODUCTION AT OPTIMAL COST.
- ALL SUBMITTED EPC DESIGNS INCLUDING ANY DEVIATIONS FROM THE DESIGN SET FORTH IN THIS DESIGN PACKAGE MUST BE APPROVED IN WRITING.
- 60/90/IFC DRAWINGS TO BE SUBMITTED TO CEH BY EPC. WRITTEN APPROVAL REQUIRED BEFORE EPC MAY PROCEED.
 - AT SUBSTANTIAL COMPLETION OF CONSTRUCTION AS-BUILT DRAWINGS TO BE SUBMITTED BY THE EPC FOR CEH. ANY DEVIATIONS FROM APPROVED DESIGN DRAWINGS MUST BE APPROVED BY CEH IN WRITING.
 - INSTALLATION SHALL COMPLY WITH LATEST STATE ADOPTED NEC, BUILDING CODE, AND ANY ADDITIONAL REQUIREMENTS AND REGULATIONS IMPOSED BY THE AHJ AND/OR ELECTRIC UTILITY.
- 7. RELAY PROTECTION SETTINGS PROVIDED ARE PRELIMINARY AND SUBJECT TO COORDINATION WITH LOCAL UTILITY.
- 8. ALL EQUIPMENT REQUIRED FOR A FULLY FUNCTIONING SYSTEM NOT MENTIONED IN THIS OR FUTURE DRAWINGS SHALL BE FURNISHED AND INSTALLED BY THE EPC AT NO ADDITIONAL COST.
- 10. ALL EQUIPMENT AND SERVICES NOT NOTED AS "TO BE PROVIDED BY OTHERS" OR "TO BE PROVIDED BY CEH" SHALL BE PROVIDED BY THE PROJECT OWNER OR EPC.
- 11. PERMISSION TO OPERATE IS NOT AUTHORIZED UNTIL COMPLETION OF COMMISSIONING/TESTING, CEH APPROVAL, APPROVAL OF AHJ, AND APPROVAL OF ELECTRIC UTILITY.
- 12. ALL ELECTRICAL EQUIPMENT SHALL CONFORM TO REQUIREMENTS OF THE NEC. WHERE UNDERWRITERS' LABORATORIES HAVE SET STANDARDS, LISTED PRODUCTS AND ISSUED LABELS, PRODUCTS USED SHALL BE LISTED AND LABELED TO THOSE STANDARDS BY UL OR ANOTHER AGENCY ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION. PRODUCTS SHALL BE INSTALLED IN ACCORDANCE WITH THE LISTING OF THE EQUIPMENT.
- 13. CONTRACTOR SHALL PROVIDE ALL REQUIRED SIGNAGE AS PER ARTICLES 690 & 705 OF THE NEC.
- 14. ELECTRICAL GROUNDING SHALL COMPLY WITH ALL REQUIREMENTS SPECIFIED ABOVE AND AT A MINIMUM INCLUDE DETAILS SHOWN IN
- 15. ALL WIRING IN PANELS SHALL BE NEATLY TIE-WRAPPED AND LIE WITHIN GUTTER SPACES.
- 16. ALL ALUMINUM TERMINATIONS NEED ANTI-OXIDATION COMPOUND APPLIED.

ELECTRICAL TESTING:

- 1. EPC SHALL PERFORM AT MINIMUM WITNESSED ELECTRICAL TESTING FOR CEH AND UTILITY FOR PERMISSION TO OPERATE.
- 2. FOR LAB CERTIFIED OR FIELD APPROVED EQUIPMENT, VERIFICATION (EITHER BY AN ON-SITE OBSERVATION OR REVIEW OF DOCUMENTS) BY THE UTILITY THAT THE INTERCONNECTION INSTALLATION EVALUATION REQUIRED BY IEEE STANDARD 1547 SECTION 5.3 AND THE COMMISSIONING TEST REQUIRED BY IEEE STANDARD 1547 SECTION 5.4 HAVE BEEN ADEQUATELY PERFORMED.
- 3. FOR INTERCONNECTION EQUIPMENT THAT HAS NOT BEEN LAB CERTIFIED OR FIELD APPROVED, THE WITNESS TEST SHALL ALSO INCLUDE THE VERIFICATION BY THE UTILITY OF THE ON-SITE DESIGN TESTS AS REQUIRED BY IEEE STANDARD 1547 SECTION 5.1 AND VERIFICATION BY THE UTILITY OF PRODUCTION TESTS REQUIRED BY IEEE STANDARD 1547 SECTION 5.2.
- 4. ALL TESTS VERIFIED BY THE UTILITY ARE TO BE PERFORMED IN ACCORDANCE WITH THE TEST PROCEDURES SPECIFIED BY IEEE STANDARD 1547.1.
- 5. ANY ADDITIONAL TESTING REQUIRED BY THE ELECTRIC UTILITY, AHJ, OR PROJECT OWNER SHALL BE PERFORMED BY THE EPC.

SYSTEM SUMMARY					
DC SYSTEM SIZE	5,922.24 kWdc				
AC SYSTEM SIZE	4,000.00 kWac				
DC/AC RATIO	1.481				
MODULES	QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV.				
MODULE QUANTITY	9,552				
INVERTERS	CHINT CPS SCH125KTL-DO/US-600 OR EQUIV.				
INVERTER QUANTITY	34				
AZIMUTH/TILT	180° / SINGLE AXIS TRACKER				
PITCH	16.2 ft				

NOT FOR CONSTRUCTION

01/04/2024

10% DESIGN

A

DRAWING TITLE GENERAL SYMBOLS

& NOTES

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852

DEVELOPER



CHECKED BY:

Vmp

Voc

WP

XFMR


PROJECT


VOLTAGE MAXIMUM POWER VOLTAGE OPEN CIRCUIT


WATT

WEATHERPROOF

TRANSFORMER







PV EQUIPMENT PAD SCALE 1/4" = 1'

SYSTEM SUMMARY 5,922.24 kWdc DC SYSTEM SIZE 4,000.00 kWac AC SYSTEM SIZE DC/AC RATIO 1.481 QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV. MODULES MODULE QUANTITY CHINT CPS SCH125KTL-DO/US-600 OR EQUIV. INVERTERS INVERTER QUANTITY 34 180° / SINGLE AXIS TRACKER AZIMUTH/TILT **PITCH** 16.2 ft

NOTES:

- 1. DRAWING FOR INTERCONNECTION APPROVAL AND EPC BID ONLY NOT FOR CONSTRUCTION.
- 2. INSTALLATION SHALL COMPLY WITH THE LATEST STATE ADOPTED NEC.
- 3. PV EQUIPMENT SHOWN FOR PRELIMINARY DESIGN ONLY. EQUIPMENT MAY BE SUBSTITUTED BY THE EPC AS APPROVED BY CEH.
- 4. PV EQUIPMENT PAD LAYOUT TYPICAL ONLY. EPC MAY SUBMIT PREFERRED LAYOUT FOR CEH APPROVAL.
- 5. INVERTERS MAY BE STACKED ONE OR TWO HIGH.
- 6. EQUIPMENT TO MEET ALL UTILITY INTERCONNECTION REQUIREMENTS.
- 7. EQUIPMENT MUST MEET ALL WORKING CLEARANCE REQUIREMENTS PER NEC 110.26 AND EQUIPMENT INSTALLATION MANUALS.

NOT FOR CONSTRUCTION

10% DESIGN

AOK

01/04/2024

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 39.2080°N, -77.4233°W

PROJECT

DEVELOPER

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852



			APPROVED BY:	DRAWING
			JSG	FO
			CHECKED BY:	~
A	CPCN UPDATE/MANDATORY REFERRAL	05/31/2024	l EJA	
	PROCESS		DESIGNED BY:	REVISION
REV.	DESCRIPTION	DATE	AOK	

DRAWING TITLE **EQUIPMENT PAD** DETAILS

DRAWING NO.

E-200 A



The 100 & 125kW high power CPS three phase string inverters are designed for ground mount applications. The units are high performance, advanced and reliable inverters designed specifically for the North American environment and grid. High efficiency at 99.1% peak and 98.5% CEC, wide operating voltages, broad temperature ranges and a NEMA Type 4X enclosure enable this inverter platform to operate at high performance across many applications. The CPS 100/125kW products ship with the Standard or Centralized Wire-box, each fully integrated and separable with AC and DC disconnect switches. The Standard Wire-box includes touch safe fusing for up to 20 strings. The CPS FlexOM Gateway enables communication, controls and remote product upgrades.

INVERTER DATA SHEET

CPS SCH100/125KTL-DO/US-600

Key Features

- NFPA 70, NEC 2014 and 2017 compliant Touch safe DC Fuse holders adds convenience and safety
- CPS FlexOM Gateway enables remote FW upgrades Integrated AC & DC disconnect switches
- 1 MPPT with 20 fused inputs for maximum flexibility Copper and Aluminum compatible AC connections





TRANSFORMER LIFTING LUGS.
TRANSFORMER GROUND PADS.
SLOPPED BOLT-ON TOP COVER WITH LIFTING EYES FOR COVER ONLY.
COOLING RADIATORS HOT DIPPED GALVANIZED UNPAINTED, BOLT-ON TYPE

(WITHOUT ISOLATION VALVES).

HV DEADBREAK BUSHING, 35KV, 200KV BIL, 600A (7).

LV EPOXY BUSHING, 1.2KV, 30KV BIL, 3010A, 10 HOLES NEMA SPADE (4).

2. LIQUID TEMPERATURE GAUGE WITHOUT CONTACTS.
3. PRESSURE VACUUM GAUGE WITH BLEEDER.
4. PRESSURE RELIEF DEVICE WITH FLAG, WITHOUT CONTACTS.

B. STAINLESS STEEL LASER PRINTED NAMEPLATE ON LV ATC DOOR.

9. PHENOLIC DUPLICATED NAMEPLATE INSIDE ATC

27. BOX FOR DRAIN VALVE. 27. BOX FOR PRESSURE RELIEF DEVICE. 28. GAUGE BOX WITH PROVISION FOR PADLOCK.

2. ELECTROSTATIC SHIELD (NOT BROUGHT OUT)

ANCHORIN BOLT HOLES

> HV CABLE ENTRY

Liquid Filled Transformer Data: MOD/SN: 452000A009W kVA: 2000 KVA AT 65°C RISE

HV: 24900 V GrdY/14376*, 125 kV BIL, 51.9A @ 2240 KVA LV: 600 V GrdY/346, 30 kV BIL, 2155A @ 2240 KVA

IMPEDANCE: 5.75 ± 7.5% WT: 19,700 LBS

—72.08—

CLASS: KNAN

BASE FOOTPRINT WITH ANCHORING

LV FRP BUSHING SUPPORT.

DOOR HOLDING BARS UP TO 120° OPENING IN BOTTOM STAINLESS STEEL HINGES FOR ATC DOORS. TRANSFORMER JACKING PAD.

COMBINATION LOWER DRAIN AND FILTER VALVE 1" NPT WITH SAMPLER.

UPPER FILTER VALVE 1" NPT AND PLUG.

PRESSURIZATION TEST POINT AND GAS SAMPLING WITH 1/2" NPT BALL VALVE LIQUID LEVEL GAUGE WITHOUT CONTACTS, GAUGE CENTER IS 25° C OIL LEVEL MARI

5. PADLOCKABLE HANDLE, DURABLE ZINC DIE CAST WITH POWDER COAT FINISH

30. MANHOLE WITH COVER, BOLTED AND GASKETED WITH PENTAHED BOLTS (2).
AND PROVISION FOR PADLOCK
11. HV/LV UNISTRUT P1000T CABLE SUPPORT.

(VTC PAINT SYSTEM IV), BASE UNDERCOATED WITH COAL-TAR EPOXY.

1. TOUCH UP PAINT KIT PROVIDED.

3. WEAK LINK FUSES 34.5 KV CURVE #9.

5. CURRENT-LIMITING BACK UP FUSES 23 KV 100A (2 PER PHASE) UNDER OIL. 7. BUSHINGS ARE EXTERNALLY CLAMPED. 8. BOTTOM OF AIR TERMINAL CHAMBER COVERED FOR SHIPMENT PURPOSES

OLES:
LIQUID FILLED TRANSFORMER INVERTER STEP UP.
ENVIROTEMP (FR3) FLUID FILLED TRANSFORMER, APPROXIMATELY 563 GALLONS.
EXTERIOR COLOR: ANSI-70, ZINC RICH PRIMER, URETHANE OVER EPOXY

D. UNIT DESIGNED FOR OPERATION AT -20 deg C.

O. UNIT DESIGNED FOR SEALED TANK OIL PRESERVATION.

1. ALL EXTERNAL BOXES HINGED WITH PENTAHEAD AND PROVISION FOR PADLOCK.

3. H0 EXTERNALLY CONNECTED BY CUSTOMER (DO NOT OPERATE WITH H0 UNGROUNDED).

LV CABLE ENTRY

kVA: 2240 KVA AT 75°C RISE

16. ALL EXTERNAL HARDWARE IS STAINLESS STEEL.
17. DO NOT USE FORKLIFT TRUCK TO HANDLING THE UNIT, THE USE OF FORKLIFT TRUCK COULD AFFECT TRANSFORMER INTEGRITY AND PERFORMANCE.

5. DE-ENERGIZED, NO LOAD MANUAL TAP CHANGER WITH PROVISION FOR PADLOCKING. 6. TWO-POSITION LOADBREAK SWITCH, 38KV, 300A, HOTSTICK OPERATED. 7. HV/LV CABINET, BOLTED ON, OPEN BOTTOM, PROVISION FOR PADLOCK AND DOOR STOP IN OPEN POSITION.

© CHINT POWER SYSTEMS AMERICA 2021/10-MKT NA

BASE OF TRANSFORMER.

■ NEMA Type 4X outdoor rated, tough tested enclosure Advanced Smart-Grid features (CA Rule 21 certified) kVA Headroom yields 100kW @ 0.9PF and 125kW @ 0.95PF Generous 1.87 and 1.5 DC/AC Inverter Load Ratios Separable wire-box design for fast service Standard 5 year warranty with extensions to 20 years 100/125KTL Centralized Wire-box

Model Name CPS SCH100KTL-DO/US-600 DC Input Max. PV Power Max. DC Input Voltage Operating DC Input Voltage Range Start-up DC Input Voltage / Power 900V / 250W Number of MPP Trackers MPPT Voltage Range¹ 870-1300Vdc Max. PV Input Current (Isc x1.25) 20 PV source circuits, pos. & neg. fused (Standard Wire-box) Number of DC Inputs 1 PV output circuit, 1-2 terminations per pole, non-fused (Centralized Wire-box DC Disconnection Type Load-rated DC switch Type II MOV (with indicator/remote signaling), Up=2.5kV, In=20kA (8/20uS) DC Surge Protection AC Output Rated AC Output Power 100kVA (111KVA @ PF>0.9) 125kVA (132KVA @ PF>0.95) Max. AC Output Power² Rated Output Voltage Output Voltage Range³ Grid Connection Type Max. AC Output Current @600Vac 96.2/106.8A 120.3/127.0A Rated Output Frequency Output Frequency Range³ Power Factor >0.99 (±0.8 adjustable) >0.99 (±0.8 adjustable) Current THD Max. Fault Current Contribution (1-cycle RMS 41.47A Max. OCPD Rating Load-rated AC switch AC Disconnection Type Type II MOV (with indicator/remote signaling), Up=2.5kV, In=20kA (8/20uS) AC Surge Protection CEC Efficiency Stand-by / Night Consumption Environment NEMA Type 4X Enclosure Protection Degree Cooling Method Variable speed cooling fans -22°F to +140°F / -30°C to +60°C (derating from +108°F / +42°C) Operating Temperature Range -40°F to +158°F / -40°C to +70°C maximum Non-Operating Temperature Range Operating Humidity 8202ft / 2500m (no derating) Operating Altitude <65dBA@1m and 25°C **Display and Communication** User Interface and Display LED Indicators, WiFi + APP Inverter Monitoring Modbus RS485 CPS FlexOM Gateway (1 per 32 inverters) Site Level Monitoring Modbus Data Mapping SunSpec/CPS Remote Diagnostics / FW Upgrade Functions Standard / (with FlexOM Gateway) Mechanical 45.28x24.25x9.84in (1150x616x250mm) with Standard Wire-box Dimensions (WxHxD) Inverter: 121lbs / 55kg; Wire-box: 55lbs / 25kg (Standard Wire-box); 33lbs / 15kg (Centralized Wire-box) 15 - 90 degrees from horizontal (vertical or angled) Mounting / Installation Angle M10 Stud Type Terminal [3Φ] (Wire range:1/0AWG - 500kcmil CU/AL, Lugs not supplied) AC Termination Screw Clamp Terminal Block [N] (#12 - 1/0AWG CU/AL) Screw Clamp Fuse Holder (Wire range: #12 - #6AWG CU) - Standard Wire-box DC Termination Busbar, M10 Bolts (Wire range: #1AWG - 500kcmil CU/AL [1 termination per pole], #1AWG - 300kcmil CU/AL [2 terminations per pole], Lugs not supplied) - Centralized Wire-box 20A fuses provided (Fuse values up to 30A acceptable) UL1741-SA-2016, CSA-C22.2 NO.107.1-01, IEEE1547a-2014; FCC PART15 Safety and EMC Standard IEEE 1547a-2014, CA Rule 21, ISO-NE Selectable Grid Standard olt-RideThru, Freg-RideThru, Ramp-Rate, Specified-PF, Volt-VAr, Freg-Watt, Volt-Watt Smart-Grid Features Warranty Standard⁶

Extended Terms 10, 15 and 20 years | See user manual for further information regarding MPPT Voltage Range when operating at non-unity PF
2) "Max. AC Apparent Power" rating valid within MPPT voltage range and temperature range of -30°C to +40°C (-22°F to +104°F) for 100KW PF ≥0.9 and 125KW PF ≥0.95
3) The "Output Voltage Range" and "Output Frequency Range" may differ according to the specific grid standard.
4) Why eneutral-grounded, Delta may not be corner-grounded.
5) See user manual for further requirements regarding non-operating conditions.
6) 5 year warrantly effective for units purchased after October 1st, 2019.

SWING DOOR


INVERTER DATA SHEET

3.2 Mechanical Installation (1) Dimensions 24.1in.(612.5mm) 21.1in.(535,5mm) [- - - -] 100/125kW Standard Wire-box (C)CPS 2::2

Figure 3-1 Dimensions of CPS SCH100/125KTL-DO/US-600 and CPS SCH100KTL-DO/US-480 Inverter

100/125kW Centralized Wire-box

INVERTER DATA SHEET



TRANSFORMER DATA SHEET

452000A009W

TRANSFORMER DATA SHEET

<u>FRONT</u>

∆ ±0.25(6.3)

Warranty Field Work:
If, at the job site, the equipment is found to have not conforme

to specifications or needs re-work covered under warranty, all parties concerned shall provide full access to Virginia Transformer Corp. or their representatives to work on the unit(s) at the job site. The method of repair/re-work will be determined

CORE GROUND

ACCESSIBLE FROM

PROJECT

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 39.2080°N, -77.4233°W

SEE NOTE 13 FOR DETAIL

WINDINGS: ALUMINUM

3 PHASE, 60 Hz TAPS: ± 2 @ 2.5 %

DEVELOPER

(8) <u>LEFT</u>

PROJECT

Customer: CHABERTON ENERGY HOLDINGS, INC

JOB NUMBER DESIGN NUMBER

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852



<u>RIGHT</u>

APPROVED BY: JSG CHECKED BY: CPCN UPDATE/MANDATORY REFERRAL 05/31/2024 **PROCESS DESIGNED BY: DESCRIPTION** DATE

10% DESIGN 01/04/2024 **DRAWING TITLE EQUIPMENT DATASHEETS REVISION**

AOK

NOT FOR CONSTRUCTION

SYSTEM SUMMARY

DC SYSTEM SIZE

AC SYSTEM SIZE DC/AC RATIO

MODULES

MODULE QUANTITY

INVERTERS

INVERTER QUANTITY

AZIMUTH/TILT

PITCH

5,922.24 kWdc

4,000.00 kWac

1.481

QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV.

CHINT CPS SCH125KTL-DO/US-600 OR EQUIV.

34

180° / SINGLE AXIS TRACKER

16.2 ft

DRAWING NO.

E-500

Q.TRON XL-G2 **SERIES**



610-635Wp | 156 Cells 22.7% Maximum Module Efficiency

The ideal solution for:

Q.TRON XL-G2 SERIES

0.08 in (2.0 mm) thermally pre-stressed glass with

MINIMUM PERFORMANCE AT NORMAL OPERATING CONDITIONS, NMOT2w

I_{MPP} [A] 10.18 V_{MPP} [V] 45.28

 Short Circuit Current
 Isc
 [A]
 11.00

 Open Circuit Voltage
 Voc
 [V]
 53.24

 $2.09\text{-}3.98\times1.26\text{-}2.36\times0.59\text{-}0.71$ in (53-101 mm \times 32-60 mm \times 15-18 mm), Protection class IP67, with bypass diodes

Bifaciality of P_{MPP} and I_{SC} 80 % \pm 5% \star Bifaciality given for rear side irradiation on top of STC (front side) \star According to IEC 60904-1-2

■ Mechanical Specification

Format 96.9 in × 44.6 in × 1.38 in (including frame)

Connector Stäubli MC4-Evo2, Stäubli MC4 ; IP68 ■ Electrical Characteristics

> Open Circuit Voltage¹ Current at MPP

Voltage at MPP Efficiency¹

Current at MPP 2800W/m2, NMOT, spectrum AM 1.5

TEMPERATURE COEFFICIENTS

Properties for System Design Maximum System Voltage V_{sys}


■ Qualifications and Certificates

Maximum Series Fuse Rating

Max. Design Load, Push/Pull3

Max. Test Load, Push/Pull3

anti-reflection technology 0.08 in (2.0 mm) semi-tempered glass Anodised aluminium



PV MODULE DATA SHEET

 Short Circuit Current*
 Isc
 [A]
 13.65
 15.13
 13.71
 15.19
 13.76
 15.25
 13.82
 15.31
 13.88
 15.38
 15.38
 13.93
 15.44

 V_{MPP} [V] 47.10 47.09 47.30 47.29 47.50 47.49 47.70 47.69 47.89 47.88 48.09 48.08 η [%] ≥21.8 ≥22.0 ≥22.2 ≥22.4 ≥22.6 ≥22.7

10.26 45.67

+0.04 Temperature Coefficient of V_{oc}

1500 PV module classification 30 Fire Rating based on ANSI/UL 61730

[lbs/ft²] 75 (3600 Pa)/33 (1600 Pa) Permitted Module Temperature

113 (5400 Pa) / 50 (2400 Pa) on Continuous Duty

Note: Installation Instructions must be followed. Contact our technical service for further information on approved installation of this product.

Hamwha Q CELLS America Inc. 400 Spectrum Center Drive, Suite 1400, Invine, CA 92618, USA | TEL. +1 949 748 59 96 | EMAIL. hqc-inquiry@qcells.com | WEB www.qcel

10.30

PERFORMANCE AT LOW IRRADIANCE

⁴ New Type is similar to Type 3 but with metallic frame



LOWER LCOE

DuraTrack® HZ v3

Three decades of field-tested design improvements have resulted in the DuraTrack® HZ v3 the most durable, reliable tracking system under the sun. While our single-bolt module clamp and forgiving tolerances streamline installation, and our flexibly linked architecture maximizes power density, it's our innovative use of fewer components and a failure-free wind management system that makes Array Technologies the best choice for solar trackers. **Better. Stronger. Smarter.**











WIND DESIGN. DuraTrack HZ v3 was Maintenance-free motors designed and field tested and gears, fewer moving profit. DuraTrack HZ v3 articulating driveline joints Array was founded on a to withstand some of the parts, and industrial-grade offers the unique ability and forgiving tolerances, philosophy of engineered harshest conditions on the components—what does density of each site, system on the market for potential failure points on the market that reliably customers? No scheduled

RELIABILITY. more power and more architecture, with to maximize the power creates the most adaptable simplicity. Minimizing planet. It is the only tracker this mean for our boasting 100 modules following natural land (167 times fewer per row and higher contours while creating components than density than our closest the greatest power generation potential

handles wind events with maintenance required. a fully integrated, fully While our competitors competitors), DuraTrack mechanical, passive average two unscheduled HZ v3 consistently wind-load mitigation maintenance events per delivers higher reliability system without the need day, we average only one and superior uptime. for complex communication per year. systems, batteries, or power.

competition.





Tracking Type	Horizontal single axis	Solar Tracking Method	Algorithm with GPS input
Less than 1 drive motor /MW	Up to 1.559 MW DC	Control Electronics	MCU plus Central
String Voltage	Up to 1,500V DC	COULT OF EIGGLOUITCS	Controller
Maximum Linked Rows	32	Data Feed	MODBUS over Ethernet to SCADA system
Maximum Row Size	116 modules crystalline, and bifacial; 240 modules First Solar 4; 90 modules First Solar 6 and 6 Plus	Night-time Stow	Yes
Drive Type	Rotating gear drive	Tracking Accuracy	± 2° standard, field adjustable
Motor Type	2 HP, 3 PH, 480V AC	Backtracking	Yes
East-West/North-South Dimensions	Site / module specific		
Array Height	54" standard, adjustable (48" min height above grade)	INSTALLATION, OPERATION &	
Ground Coverage Ratio (GCR)	Flexible, 28–45% typical, others supported on request	Software	SmarTrack optimization available
Terrain Flexibility	N-S tolerance: 0-15% standard, 26% optional; Driveline: 40° in all directions	PE Stamped Structural	Vac
Modules Supported	Most commercially available, including frameless crystalline, thin film, and bifacial	Calculations & Drawings On-site Training and	Yes
Tracking Range of Motion	± 52° standard, ± 62° optional	System Commissioning	Yes
Operating Temperature Range	-30°F to 140°F (-34°C to 60°C)	Connection Type	Fully bolted connections, no welding
Module Configuration available.	Single-in-portrait standard, including bifacial. Four-in-landscape (thin film)	In-field Fabrication Required	No
Module Attachment	Single fastener, high-speed mounting clamps with integrated grounding. Traditional rails for crystalline in landscape, custom racking for thin film and	Dry Slide Bearings and Articulating Driveline Connections	No lubrication required
	frameless crystalline and bifacial per manufacturer specs.	Scheduled Maintenance	None required
Materials	Pre-galv steel, HDG steel and aluminum structural members, as required	Module Cleaning Compatibility	Robotic, Tractor, Manual
Allowable Wind Load (ASCE 7-10)	140 mph, 3-second gust exposure C		Hidiladi
Wind Protection	Failure free passive mechanical system protects against wind damage without the use	GENERAL	
	of complex communications systems, batteries — no power required	Annual Power Consumption (kWh per 1 MW)	400 kWh per MW per vear, estimate

PV TRACKER DATA SHEET



includes increasing power density. But most of all, differences that keep your system running sales@arraytechinc.com value is measured in operational uptime, or reliability. flawlessly all day and you resting easy at night. arraytechinc.com

STRUCTURAL & MECHANICAL F	EATURES/SPECIFICATIONS	ELECTRONIC CONTROLLER FEAT	URES/SPECIFICATIONS
Tracking Type	Horizontal single axis	Solar Tracking Method	Algorithm with GPS input
Less than 1 drive motor /MW	Up to 1.559 MW DC	Control Electronics	MCU plus Central
String Voltage	Up to 1,500V DC	Control Eloctronics	Controller
Maximum Linked Rows	32	Data Feed	MODBUS over Ethernet to SCADA system
Maximum Row Size	116 modules crystalline, and bifacial: 240 modules First Solar 4: 90 modules First Solar 6 and 6 Plus	Night-time Stow	Yes
Drive Type	Rotating gear drive	Tracking Accuracy	± 2° standard, field adjustable
Motor Type	2 HP, 3 PH, 480V AC	Backtracking	Yes
East-West/North-South Dimensions	Site / module specific		
Array Height	54" standard, adjustable (48" min height above grade)	INSTALLATION, OPERATION &	
Ground Coverage Ratio (GCR)	Flexible, 28–45% typical, others supported on request	Software	SmarTrack optimization available
Terrain Flexibility	N-S tolerance: 0-15% standard, 26% optional; Driveline: 40° in all directions	PE Stamped Structural	V
Modules Supported	Most commercially available, including frameless crystalline, thin film, and bifacial	Calculations & Drawings On-site Training and	Yes
Tracking Range of Motion	± 52° standard, ± 62° optional	System Commissioning	Yes
Operating Temperature Range	-30°F to 140°F (-34°C to 60°C)	Connection Type	Fully bolted connections, no welding
Module Configuration available.	Single-in-portrait standard, including bifacial. Four-in-landscape (thin film)	In-field Fabrication Required	No
Module Attachment	Single fastener, high-speed mounting clamps with integrated grounding. Traditional rails for crystalline in landscape, custom racking for thin film and	Dry Slide Bearings and Articulating Driveline Connections	No lubrication required
	frameless crystalline and bifacial per manufacturer specs.	Scheduled Maintenance	None required
Materials	Pre-galv steel, HDG steel and aluminum structural members, as required	Module Cleaning Compatibility	Robotic, Tractor, Manual
Allowable Wind Load (ASCE 7-10)	140 mph, 3-second gust exposure C		manuai
Wind Protection	Failure free passive mechanical system protects against wind damage without the use	GENERAL	
	of complex communications systems, batteries — no power required	Annual Power Consumption (kWh per 1 MW)	400 kWh per MW per year, estimate

AOS-99-DS-0002 - REV 1.2 - 18NOVEMBER2020

PROJECT

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 39.2080°N, -77.4233°W

DEVELOPER

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852



				1(
			APPROVED BY:	D
			JSG CHECKED BY:	
Α	CPCN UPDATE/MANDATORY REFERRAL PROCESS	05/31/2024	EJA DESIGNED BY:	R
				1

DATE

AOK

DESCRIPTION

CONSTRUCTION 10% DESIGN 01/04/2024 DRAWING TITLE **EQUIPMENT**

NOT FOR

SYSTEM SUMMARY

DC SYSTEM SIZE **AC SYSTEM SIZE**

DC/AC RATIO

MODULES MODULE QUANTITY

INVERTERS

INVERTER QUANTITY

AZIMUTH/TILT

PITCH

5,922.24 kWdc

4,000.00 kWac

QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV.

CHINT CPS SCH125KTL-DO/US-600 OR EQUIV.


34


180° / SINGLE AXIS TRACKER

16.2 ft

DATASHEETS REVISION DRAWING NO.

E-501





NOTES:

- 1. DRAWING IS DIAGRAMMATIC AS SHOWN AND INTENDED TO COMMUNICATE
- 2. PILE SURVEYING SHALL BE PERFORMED BY A LICENSED SURVEYOR USING
- THE APPLICABLE STATE-PLANE COORDINATE SYSTEM. 3. EPC TO DETERMINE PILE EMBEDMENT AND FOUNDATIONS PER STRUCTURAL
- CALCULATIONS FOR EACH TORQUE TUBE HEIGHT AND BASE 4. FOUNDATION AND RACKING SHALL BE INSTALLED PER MANUFACTURER'S
- INSTALLATION MANUAL AND WITHIN STATED TOLERANCES. 5. ALL GRADING AND DRAINAGE SHALL BE PER CIVIL CONSTRUCTION
- DRAWINGS. 6. EPC TO DETERMINE RACKING SPACING
- 7. ALL STRUCTURAL AND MECHANICAL DESIGNS TO BE PERFORMED BY A QUALIFIED LICENSED PROFESSIONAL ENGINEER.
- 8. DESIGN CRITERIA:
- 8.1. 105 MPH WIND SPEED, ASCE 7-10, CAT I OR COUNTY MINIMUM REQUIREMENTS; WHICHEVER IS HIGHER
- 8.2. 25 PSF GROUND SNOW EXPOSURE OR COUNTY MINIMUM REQUIREMENTS;
- WHICHEVER IS HIGHER 8.3. ANCHORING IS PILE DRIVEN UNLESS OTHERWISE REQUIRED BY SITE
- CONDITIONS.
- 8.4. PANELS AZIMUTH TO BE 180°
- 8.5. FINAL DESIGN MAY BE ADJUSTED PRIOR TO CONSTRUCTION. MAXIMUM HEIGHT NOT TO BE INCREASED WITHOUT APPROVAL FROM THE ENGINEER
- 8.6. <20% OF LEADING EDGES TO BE WITHIN 2' OF GROUND FOR PURPOSES OF POLLINATOR GROWTH.
- 8.7. <5% OF TORQUE TUBE TO BE >8' ABOVE GROUND ELEVATION.
- 8.8. RACKING TO BE SINGLE PORTRAIT ORIENTATION.
- 9. MAXIMUM RACKING TOLERANCE ASSUMED AT 15%

TYP. MODULE INTERIOR ROW SCALE 1/4" = 1'

PROJECT

CHABERTON SOLAR SUGARLOAF LLC 5.92 MWdc / 4.00 MWac GROUND MOUNT AT 20507 DARNESTOWN RD. DICKERSON, MD 20842 39.2080°N, -77.4233°W

DEVELOPER

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852



			CHEC
В	CPCN UPDATE/MANDATORY REFERRAL PROCESS	05/31/2024	DESIG
DE\/	DESCRIPTION	DATE	

EJA

APPROVED BY:

DRAWING TITLE RACKING DETAILS

01/04/2024

NOT FOR


CONSTRUCTION

REVISION DRAWING NO.

10% DESIGN

M-001

DESCRIPTION AOK DATE



SYSTEM SUMMARY				
	DC SYSTEM SIZE	5,922.24 kWdc		
	AC SYSTEM SIZE	4,000.00 kWac		
	DC/AC RATIO	1.481		
	MODULES	QCELL Q.TRON XL-G2 620 (620Wp) OR EQUIV.		
	MODULE QUANTITY	9,552		
	INVERTERS	CHINT CPS SCH125KTL-DO/US-600 OR EQUIV.		
	INVERTER QUANTITY	34		
	AZIMUTH/TILT	180° / SINGLE AXIS TRACKER		
	DITOLI	40.0 %		


LAYER LEGEND

PROP UNDERGROUND ELECTRIC		JGE	- UGE -	- UGE -	– UGE ––––
PROP OVERHEAD ELECTRIC	(DHE -	- OHE	- OHE -	— OHE ————
EX UNDERGROUND ELECTRIC		JGE ————	- UGE	– UGE –	— UGE ————
EX OVERHEAD ELECTRIC	(DHE	- OHE	– OHE –––––	— OHE ————
PROP FENCE		0 —	- 0	- 0 —	- 0
PROPERTY LINE					
SOLAR PV MODULES					


ELEVATION TABLE							
COLOR	MIN HEIGHT	MAX HEIGHT	AREA (sf)	PERCENT AREA			
	4.274	5.180	43,531	14.49%			
	5.180	5.500	60,579	20.16%			
	5.500	6.000	71,159	23.68%			
	6.000	6.500	44,619	14.85%			
	6.500	7.000	35,817	11.92%			
	7.000	7.500	27,707	9.22%			
	7.500	8.000	8,083	2.69%			
	8.000	9.738	8,976	2.99%			

- . MINIMAL GRADING NECESSARY FOR CONSTRUCTION OF ROADS AND
- TRANSFORMERS ARE TO BE BALANCED ON-SITE.

 2. ELEVATIONS ARE MEASURED FROM THE LONGITUDINAL MIDPOINT OF THE ARRAY TO THE GROUND ELEVATION.




AREA OF FILL: 1.16 FT DEPTH



AREA OF CUT: 0.75 FT DEPTH

NOTE: THERE IS APPROXIMATELY 1,600 CY OF CUT AND 1,600 CY OF FILL GRADING NECESSARY FOR CONSTRUCTION OF ROADS AND TRANSFORMERS ARE TO BE BALANCED ON-SITE.



NOT FOR CONSTRUCTION

10% DESIGN

01/04/2024

DRAWING TITLE

JSG PLANAR STUDY

EJA DRAWING NO. REVISION

CHABERTON ENERGY 1700 Rockville Pike, Suite 305 Rockville, MD 20852

20507 DARNESTOWN RD. DICKERSON, MD 20842

39.2080°N, -77.4233°W



CPCN UPDATE/MANDATORY REFERRAL 05/31/2024 PROCESS

DESCRIPTION DATE


DESIGNED BY: AOK

В

M-101

DRAWINGS FOR CONCEPT STORMWATER PLAN SUGARLOAF 4.0 MW AC SOLAR PROJECT

DICKERSON, MONTGOMERY COUNTY, MARYLAND



Base map from MDOT SHA's State of Maryland Official Transportation Map **VICINITY MAP**

PREPARED FOR DEVELOPER: CHABERTON SOLAR SUGARLOAF LLC 1700 ROCKVILLE PIKE, SUITE 305 ROCKVILLE, MD 20852 (804) 929-8418

PROPERTY OWNER: DOUGLAS BOUCHER 20507 DARNESTOWN ROAD DICKERSON, MD 20842

SITE ADDRESS:

20507 DARNESTOWN ROAD, DICKERSON, MD 20842 (39.2080°N, -77.4233°W)

PROJECT SITE:

- 1. EXISTING ZONING: AGRICULTURAL RESERVE (AR) ZONE EXISTING USE: AGRICULTURAL
- 3. PROPOSED USE: COMMUNITY SOLAR ENERGY GENERATING SYSTEM (CSEGS)
- 4. TOTAL SITE AREA: 52.46 AC
- 5. TOTAL PROPOSED DEVELOPMENT AREA (LIMIT OF DISTURBANCE): 860,462 SF (19.8± AC)
- 6. TAX MAP NO. 11-03023873, DEED BOOK: 12458, PAGE: 017 7. SYSTEM SIZE: 5,886 kW DC / 4,000 kW AC

MISS UTILITY

CALL "MISS UTILITY" AT 1-800-257-7777, 48 HOURS PRIOR TO THE START OF WORK. THE EXCAVATOR MUST NOTIFY ALL PUBLIC UTILITY COMPANIES WITH UNDER GROUND FACILITIES IN THE AREA OF PROPOSED EXCAVATION AND HAVE THOSE FACILITIES LOCATED BY THE UTILITY COMPANIES PRIOR TO COMMENCING EXCAVATION. THE EXCAVATOR IS RESPONSIBLE FOR COMPLIANCE WITH REQUIREMENTS OF CHAPTER 36A OF THE MONTGOMERY COUNTY CODE.

JULY 2024

LIST OF SHEETS

DESCRIPTION

- EXISTING SITE CONDITIONS PLAN
- PROPOSED SITE CONDITIONS PLAN (SHEET 1 OF 2)

PROPOSED SITE DETAILS (SHEET 2 OF 2)

- PROPOSED SITE CONDITIONS PLAN (SHEET 2 OF 2)
- PROPOSED SITE DETAILS (SHEET 1 OF 2)

ugust	2023	
-		

				R OF THIS SITE TO OBTA EDIMENT CONTROL PER	
TYPE OF PERMIT	REQD	NOT REQD	PERMIT #	EXPIRATION DATE	WORK RESTRICTION DATES
MCDPS Floodplain District		Х			
WATERWAYS/WETLAND(S):		Х			
a. Corps of Engineers					
b. MDE					
c. MDE Water Quality Certification					
MDE Dam Safety		Х			
MSCD Small Pond Approval		Х			
* DPS Roadside Trees Protection Plan		Х		Approval Date	
**N.P.D.E.S. NOTICE OF INTENT	х				
FEMA LOMR (Required Post Construction)		Х			
OTHERS (Please List):					

*A copy of the approved Roadside Trees Protection Plan must be delivered to the Sediment Control Inspector at the Preconstruction

**When a Notice of Intent is required, the sediment control permit may not be issued until confirmation of authorization under the MDE's 20-CP permit has been submitted to DPS.

OWNER'S/DEVELOPER'S CERTIFICATION

I/We hereby certify that all clearing, grading, construction, and or development will be done pursuant to this plan and that any responsible personnel involved in the construction project will have a Certificate of Attendance at a Department of Natural Resources approved training program for the control of sediment and erosion before beginning the project.

Printed Name and Title

SWM Concept Summary Table: Contact Information for Design Engineer (for technical issues): Charles Walker ARM Group LLC 9175 Guilford Road Suite 310 Columbia, MD 21046 Phone: 667-240-2533 General Property Information: SM# 293586 Type of Concept: SWM Concept MNCP&PC Process/No: Mandatory Referral Property Address: 20507 Darnestown Road Dickerson, MD 20842 Property Legal Description: Parcel 127 Property Size (ac/sq. ft.): 52.46 ac/ 2,284,997 sq. ft. Total Concept Area (ac./sq. ft.): 19.8 ac. / 860,462 sq. ft. Zoning: AR (Agricultural Reserve) Watershed(s) and Stream Class: Middle Potomac River Watershed/ Class I-P Special Protection Area: r 100 YR Floodplain: FEMA 24031C0135D Ex. % impervious / Redevelopment or New Development: 5% impervious / New Development SWM Summary: Target PE/Proposed PE: 1.0" / 3.44" Target ESDv/Provided ESDv: 7,067 cf / 24,309 cf ESD Measures: Non-rooftop Disconnec Structural Storage Required/Provided: n/ Structural Measures: n/a Waiver Request/QL/QN/Both: No Provided ESDv + Structural Storage Provided + Requested to be Waived = 24,309 cf Other Information:

I hereby certify that the estimated total amount of excavation and fill as shown on these plans has been computed to ________ cubic yards of excavation, _______ cubic yards of fill and the total area to be disturbed as shown on these plans has been determined to be _______ square feet.

CERTIFICATION OF THE QUANTITIES

world has Printed Name and Title Registration Number


DESIGN CERTIFICATION

I hereby certify that this plan has been prepared in accordance with the "2011 Maryland Standards and Specification for Soil Erosion and Sediment Control," Montgomery County Department of Permitting Services Executive Regulations 5-90, 7-02AM and 36-90, and Montgomery County Department of Public Works and Transportation "Storm Drain Design Criteria" dated August 1988.

(world Ga Design Engineer Signature

Printed Name

7/31/24 Registration Number



LOCATION MAP

ARM Group LLC **Engineers and Scientists**

HEADQUARTERS: 1129 West Governor Road • Hershey, PA 17033-0797


Ph: (717) 533-8600 Fax: (717) 533-8605


www.armgroup.net


NOT FOR CONSTRUCTION CHARLES D. WALKER, P.E. NO. 61081 ROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT ME. AND THAT I A AM DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLANI LICENSE NO. 61081 , EXPIRATION DATE: 05-11-25


Base map from the following USGS 7½ minute quadrangle: Poolesville, MD, VA dated 2023.


PREPARED BY:











- 2. EXCAVATE OR SHAPE EARTH DIKE TO LINE, GRADE, AND CROSS SECTION AS SPECIFIED. BANK PROJECTIONS OR OTHER IRREGULARITIES ARE NOT ALLOWED.
- 4. CONSTRUCT FLOW CHANNEL ON AN UNINTERRUPTED, CONTINUOUS GRADE, ADJUSTING THE LOCATION DUE TO FIELD CONDITIONS AS NECESSARY TO MAINTAIN POSITIVE DRAINAGE.
- 5. PROVIDE OUTLET PROTECTION AS REQUIRED ON APPROVED PLAN.
- 6. STABILIZE EARTH DIKE WITHIN THREE DAYS OF INSTALLATION. STABILIZE FLOW CHANNEL FOR CLEAR WATER DIVERSION WITHIN 24 HOURS OF INSTALLATION.
- MAINTAIN LINE, GRADE, AND CROSS SECTION. REMOVE ACCUMULATED SEDIMENT AND DEBRIS, AND MAINTAIN POSITIVE DRAINAGE. KEEP EARTH DIKE AND POINT OF DISCHARGE FREE OF EROSION, AND CONTINUOUSLY MEET REQUIREMENTS FOR ADEQUATE VEGETATIVE ESTABLISHMENT IN ACCORDANCE WITH SECTION B-4 VEGETATIVE STABILIZATION.
- 3. UPON REMOVAL OF EARTH DIKE, GRADE AREA FLUSH WITH EXISTING GROUND. WITHIN 24 HOURS OF REMOVAL STABILIZE DISTURBED AREA WITH TOPSOIL, SEED, AND MULCH, OR AS SPECIFIED ON APPROVED PLAN.

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL U.S. DEPARTMENT OF AGRICULTURE MARYLAND DEPARTMENT OF ENVIRONMENT 2011 NATURAL RESOURCES CONSERVATION SERVICE WATER MANAGEMENT ADMINISTRATION

C.5



- A VERIFICATION OF SITE STAKING AND LAYOUT SHALL BE CONDUCTED PRIOR TO EXCAVATION
- ALL EXCAVATION, BACKFILL, AND COVER SHALL BE PERFORMED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. DIMENSIONS AND DETAILS SHOWN ARE FOR REFERENCE AND SHALL NOT SUPERSEDE MANUFACTURER'S REQUIREMENTS. EXCAVATION DEPTH SHALL BE DETERMINED BY SITE CONDITIONS AND MANUFACTURER'S SPECIFICATIONS. SHORE AS NECESSARY. ELEVATIONS SHOWN IN TABLE 2 REPRESENT THE MAXIMUM ALLOWABLE CONDITION FOR
- PROPER TANK OPERATION AND SHALL NOT BE EXCEEDED. ALL WORK SHALL BE COMPLETED IN A TIMELY AND WORKMANLIKE MANNER. ALL WORK SHALL CONFORM TO APPLICABLE CODES AND
- EXCAVATION AND SITE WORK SHALL BE PERFORMED IN ACCORDANCE
- WITH APPLICABLE AND CURRENT OSHA AND MOSHA REGULATIONS. PRESSURE TEST PROCEDURES SHALL BE PERFORMED BY THE INSTALLER PRIOR TO AND AFTER INSTALLATION IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- AN OPERATIONAL TEST SHALL BE CONDUCTED AFTER INSTALLATION PER THE SPECIFICATIONS.
- ALL STEEL PIPING BELOW GRADE SHALL BE WRAPPED AND COATED WITH AN APPROVED MATERIAL TO PREVENT CORROSION.
- ALL STEEL AND PVC PIPE AND FITTINGS ABOVE GRADE SHALL BE PAINTED WITH EXTERIOR ENAMEL. UNLESS OTHERWISE SPECIFIED,
- COLOR YELLOW. INSTALLER SHALL RETURN SITE TO ORIGINAL CONDITION AFTER FINAL
- TESTING, INCLUDING BUT NOT LIMITED TO FINE GRADING, SEEDING, MULCHING AND GENERAL CLEANUP
-). DISTANCE FROM THE CENTERLINE OF THE DRAFT FITTING SHALL BE 7' 0" OR LESS TO THE EDGE OF THE ROADWAY OR PULLOFF. THIS DIMENSION SHALL APPLY TO BOTH -1 AND -2 CONFIGURATIONS.

. WATER LEVEL INDICATOR ON THE VENT ASSEMBLY SHALL BE ORIENTED


- TOWARD THE ACCESS AREA OR PULLOFF FOR VISIBILITY. 2. INSTALL POST AND DOT R7 STYLE NO PARKING SIGN. TOP OF POST
- SHALL BE 7' ABOVE GRADE. 3. UNLESS OTHERWISE SPECIFIED, 4" DIA. CONCRETE FILLED PIPE BOLLARDS SHALL BE PLACED AS SHOWN TO PROTECT FITTINGS NEAR TRAFFIC AREAS. BOLLARDS SHALL BE PAINTED FOR HIGH VISIBILITY.
- PLACE BOLLARDS 12" FROM EDGES OF CONCRETE SLAB AND NO DEEPER THAN 1/2 DEPTH OF FILL OVER TANK. 4. VARIATION IN FITTING LOCATIONS OF UP TO 10" FROM DIMENSIONS SHOWN ARE ALLOWABLE IN TANKS FROM DIFFERENT VENDORS. SECTION NUMBERS USED WILL BE THE SAME, THE BASIC

CONFIGURATION AND CRITICAL DIMENSIONS SHALL BE MAINTAINED


APPROVED BY THE DESIGN ACTIVITY PRIOR TO INSTALLATION. MANWAY EXTENSION SHALL BE ADJUSTED FOR HEIGHT TO PLACE THE TOP OF BOLT COVER WITHIN AND NO LOWER THAN THE BOTTOM OF THE MANHOLE FRAME.


TABLE 1 - FITTING SCHEDULE							
FITTING	SPECIFICATION	-1 CENT	ER DRAFT	-2 END DRAFT			
	SPECIFICATION	SECTION	OFFSET	SECTION	OFFSET		
DRAFT	6" NST FULL COUPLING	16	20' - 7 ½"	1	0'-0"		
FILL	4" NST HALF COUPLING	6	6' - 10 ½"	6	6' - 10 ½"		
VENT	10" CLASS 150 FLANGE	10	12' - 4 ½"	10	12' - 4 ½"		
MANWAY	32" MANWAY, EXTENSION, 4" NPT COUPLING AND PLUG	12/13	15' - 9 ³ / ₄ "	12/13	15' - 9 ½"		

TABLE 2 - ELEVATIONS					
ELEVATION	DESCRIPTION				
15' - 0" MAX	DRAFT PIPE CENTERLINE				
13' - 0"	TOP OF SLAB				
0	BOTTOM OF TANK				
-10"	BOTTOM OF EXCAVATION				



HYDRANT HEAD ASSEMBLY






C.24

NATURAL RESOURCES CONSERVATION SERVICE

WATER MANAGEMENT ADMINISTRATION



818-LA-10 8'-0" 18'-0" 9'-4" 19'-4" 818-B 26,200 lbs. 818-R-60" 28,150 lbs. 1020-LA-10 10'-0" 40'-0" 11'-4" 41'-4" 1020-B 35,290 lbs. 1020-R-60" 32,800 lbs. 1022-LA-10 10'-0" 22'-0" 11'-4" 23'-4" 1022-B 38,620 lbs. 1022-R-60" 33,300 lbs. 1022-T-42EE 35,770 lbs.


Note: Designed for 0 to 2'-0" of Cover Oldcastle Precast* PO Box 323, Wilsonville, Oregon 97070-0323


SECTIONAL VAULT File Name: 020-LG-SECTIONAL Issue Date: 2016 Tel: (503) 682-2844 Fax: (503) 682-2657 oldcastleprecast.com/wilsonville

- SIZE AS REQUIRED -WATER MODIFIED

SECTIONAL VAULT

FIRE SUPPRESSION TANK DETAIL





CONSTRUCTION SPECIFICATIONS


OF THE SUPER SILT FENCE.


- INSTALL 2% INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AND SIX FOOT LENGTH SPACED NO FURTHER THAN 10 FEET APART. DRIVE THE POSTS A MINIMUM OF 36 INCHES
- 2. FASTEN 9 GAUGE OR HEAVIER GALVANIZED CHAIN LINK FENCE (23/8 INCH MAXIMUM OPENING) 42 INCHES IN HEIGHT SECURELY TO THE FENCE POSTS WITH WIRE TIES OR HUG RINGS.
- 3. FASTEN WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS, SECURELY TO THE UPSLOPE SIDE OF CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 8 INCHES INTO THE GROUND.
- 4. WHERE ENDS OF THE GEOTEXTILE COME TOGETHER, THE ENDS SHALL BE OVERLAPPED BY 6 INCHES, FOLDED, AND STAPLED TO PREVENT SEDIMENT BY PASS.
- 5. EXTEND BOTH ENDS OF THE SUPER SILT FENCE A MINIMUM OF FIVE HORIZONTAL FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT TO PREVENT RUNOFF FROM GOING AROUND THE ENDS
- 5. PROVIDE MANUFACTURER CERTIFICATION TO THE INSPECTION/ENFORCEMENT AUTHORITY SHOWING THAT GEOTEXTILE USED MEETS THE REQUIREMENTS IN SECTION H-1 MATERIALS.
- REMOVE ACCUMULATED SEDIMENT AND DEBRIS WHEN BULGES DEVELOP IN FENCE OR WHEN SEDIMENT REACHES 25% OF FENCE HEIGHT. REPLACE GEOTEXTILE IF TORN. IF UNDERMINING OCCURS, REINSTALL
- CHAIN LINK FENCING AND GEOTEXTILE. MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

U.S. DEPARTMENT OF AGRICULTURE MARYLAND DEPARTMENT OF ENVIRONMENT NATURAL RESOURCES CONSERVATION SERVICE WATER MANAGEMENT ADMINISTRATION




LARGE SECTIONAL VAULT





RISER JOINT DETAIL



VARIABLE SIZE CHART						
Vault No.	А	В	С	D	E	F
620-LA-10	21'-4"	20'-0"	7'-4"	6'-0"	10'-0"	11'-8"
818-LA-10	19'-4"	18'-0"	9'-4"	8'-0"	10'-0"	11'-8"
1020-LA-10	41'-4"	40'-0"	11'-4"	10'-0"	10'-0"	11'-8"
1022-LA-10	23'-4"	22'-0"	11'-4"	10'-0"	10'-0"	11'-8"
1024-LA-10	25'-4"	24'-0"	11'-4"	10'-0"	10'-0"	11'-8"



SECTIONAL VAULT

SECTIONAL VAULT SIZE AS REQUIRED -WATER **MODIFIED**



This drawing, its contents, and each component of this drawing are the property of and proprietary to ARM Group LLC and shall not be reproduced or used in any manner except for the purpose identified on the Title Block, and only by or on behalf of this client for the identified project unless otherwise authorized by the express, written consent of ARM Group LLC.







